

# AL'S Concrete Products, Inc.

800 Town Hall Road • La Crescent, MN 55947

(507) 895-4509

1-800-982-9263

Fax: 507- 895-6805

## Bunker Silo Site Preparation

With our experience of installing Bunker Silos for over 35 years there should be a minimum of ½% to 2% slope on the Bunker Silo site. We also recommend using a 1" to 2" diameter screen rock or gravel under each wall app. 8" thick covering a 4" tile line with a gravity outlet.

The reason for this is to keep the soil dry under the wall for better stability and to keep excess moisture and rain water out of the feed so you will be able to achieve a higher quality of feed.

If you do not use the drain tile we still recommend an 8" compacted gravel base under each wall for stability. This could vary according to soil conditions.

The site should be rough graded to 1" of final grade. When we come to erect the walls our crew will do the final grading. The customer will have to furnish Al's Concrete with a skid loader and fine gravel (3/8" or less) to do the final grading.



